PANEL 107RP_1 | FED FROM | CKT #

LOCATION ROOM 107 | MOUNTING Recessed | PHASE 3 | WIRE 4 | FEEDER | BUS 100 | VOLTS 208Y/120V | MAIN

CKT	LOAD SERVED	SLOT	POLES	WIRE SIZE	TRIP	VOLT AMPS	PHASE LOAD (VA) A	B	C	VOLT AMPS	TRIP	WIRE SIZE	POLES	SLOT	LOAD SERVED	CKT
1	VEST. LIGHTS 103	1	1	12	20						12	20	1	2	107 RECEPT.	2
3	106 RECEPT.	3	1	12	20						0	20	1	4	SPARE	4
5	VANE ACT. DAMPERS	5	1	12	20						0	20	1	6	SPARE	6
7	AH LIGHTS	7	1	12	20						12	20	1	8	SPARE	8
9	AH LIGHTS	9	1	12	20						0	20	1	10	SPARE	10
11	AH LIGHTS	11	1	12	20						12	20	1	12	GLYCOL PUMP SYS.	12
13	SPARE	13	1	0	20						12	20	1	14	HVAC SYS. CONTROL	14
15	SPARE	15	1	0	20						0	20	1	16	SPARE	16
17	SPARE	17	1	0	20						0	20	1	18	SPARE	18
19	SPARE	19	1	0	20						0	20	1	20	SPARE	20
21	SPARE	21	1	0	20						0	20	1	22	SPARE	22
23	SPARE	23	1	0	20						0	20	1	24	SPARE	24
25	SPARE	25	1	0	20						0	20	1	26	SPARE	26
27	SPARE	27	1	0	20						0	20	1	28	SPARE	28
29	SPARE	29	1	0	20						0	20	1	30	SPARE	30
						TOTAL										

TOTAL CONNECTED LOAD (VA)
(AMPS)

PANEL 107LP_1 | FED FROM | CKT #

LOCATION ROOM 107 | MOUNTING Recessed | PHASE 3 | WIRE 3 | FEEDER | BUS 225 | VOLTS 480Y/277V | MAIN

CKT	LOAD SERVED	SLOT	POLES	WIRE SIZE	TRIP	VOLT AMPS	PHASE LOAD (VA) A	B	C	VOLT AMPS	TRIP	WIRE SIZE	POLES	SLOT	LOAD SERVED	CKT
1	102 OVERHEAD LTS	1	1	10	20						20	0	1	2	SPARE	2
3	102 EM. EXIT LTS	3	1	10	20						20	10	1	4	106 OVERHEAD LTS	4
5	103 OVERHEAD LTS	5	1	10	20						20	10	1	6	106 EM. EXIT LTS	6
7	103 EM. EXIT. EXT. LTS	7	1	10	20						20	0	1	8	SPARE	8
9	104 OVERHEAD LTS	9	1	10	20						20	10	1	10	107 EXIT. EM LTS	10
11	104,105 EM. EXIT. EXT. LTS	11	1	10	20						20	10	1	12	107 OVERHEAD LTS	12
13	SPARE	13	1	0	20						20	0	1	14	SPARE	14
15	107 OVERHEAD LTS	15	1	10	20						20	0	1	16	SPARE	16
17	SPARE	17	1	0	20						20	10	1	18	107 LIGHTS	18
19	ROLL UP DOORS	19	3	10	20						70	1/0	3	20	XMFR W-CS-107	20
		21									70	1/0		22		
		23									70	1/0		24		
25	SPARE	25	1	0	20	0	0	0	0	0	20	0	1	26	SPARE	26
27	SPARE	27	1	0	20	0	0	0	0	0	20	0	1	28	SPARE	28
29	SPARE	29	1	0	20	0	0	0	0	0	20	0	1	30	SPARE	30
						TOTAL										

TOTAL CONNECTED LOAD (VA)
(AMPS)

This document and the design it covers are the property of PARSONS. They are loaned only with the borrower's expressed written agreement that they will not be reproduced, copied, loaned, exhibited, or used in any other way, except by written consent from PARSONS to the borrower.

REFERENCES

DRAWING NO.	DESCRIPTION

REVISIONS

NO.	DATE	BY	CHKD	ENGR	PROJ	DESCRIPTION
1	6-15-98	J. G.				ISSUED FOR AS-BUILT

ISSUED FOR CONSTRUCTION

DRAWN	M. M.	6-25-96
CHECKED	J. K.	7-3-96
ENGINEER	K. R.	7-3-96
PROJ	M. D. W.	7-8-96

AS-BUILT DRAWINGS

PARSONS
100 WEST WALNUT STREET
PASADENA, CALIFORNIA

LIGO
CALIFORNIA INSTITUTE OF TECHNOLOGY
MASSACHUSETTS INSTITUTE OF TECHNOLOGY

LIGO-D960406-01-O

LASER INTERFEROMETER
GRAVITATIONAL-WAVE OBSERVATORY
SITE NO. 1 - HANFORD, WASHINGTON

TITLE
ELECTRICAL CORNER STATION MECH. RM. LIGHTING AND POWER PANEL SCHEDULES

SCALE	CONTRACT NUMBER	PROJECT NUMBER
NONE	PP150969	8094

SHEET NUMBER **WA-E-117**

REVISIONS 1

LIGOWAF3.BDR

Thu Jul 09 13:41:14 1998 C:\PLOT\QUE\S3-V3682.QCF 52085 K1V3682\ee117.aprf