INPUT/OUTPUT SUMMARY FOR PLUMBING & FIRE PROTECTION PUMPS AT CORNER STATION

SYSTEM, APPARATUS, OR AREA POINT DESCRIPTION	INPUTS: ANALOG MEASURED: TEMPERATURE	PRESSURE	RH	KW	AIR FLOW	LEVEL	GALLONS	VIBRATIONS	INPUTS: ANALOG CALCULATED: KWH	ENTHALPY	RUN TIME	EFFICIENCY	WET BULB TEMP.	INPUTS: BINARY: STATOS	FILTER	SMOKE	FREEZE	AIR FLOW	METER	OUTPUTS: DIGITAL: OFF-ON	OFF-AUTO-ON	OFF-HI-LO	OPEN-CLOSE	MULTI-STAGE	OUTPUTS: ANALOG: DAMPER POSITION	VALVE POSITION	SET POINT ADJUSTMENT	VANE POSITION	SCR CONTROL	SYSTEM FEATURES: ALARMS: HI ANALOG	LOW ANALOG	HI BINARY	LOW BINARY	PROOF	SYSTEM FEATURES: PROGRAMS: TIME SCHEDULING	DEMAND LIMITING	DUTY CYCLE	START/STOP OPTION	ENTHALPY OPTION	SMOKE CNT.	TREND	ALARM INSTRUCT	MAINT. WK. ORD.	GENERAL: COLOR GRAPHIC	SUPPLEMENTARY NOTES
DOMESTIC WATER PUMP, DP-04								●		●				●						●																					●			
DOMESTIC WATER PUMP, DP-05								●		●				●						●																					●			
DOMESTIC WATER PRESSURE		●																												●											●			
DOMESTIC WATER STORAGE TANK LEVEL						●																								●											●			
FIRE WATER STORAGE TANK LEVEL						●																								●											●			
FIRE WATER PUMP, FP-01														●																											●	●		CURRENT SWITCH
FIRE WATER PUMP, FP-02														●																											●	●		CURRENT SWITCH
FIRE WATER JOCKY PUMP, JP-03														●																											●	●		CURRENT SWITCH
FIRE WATER PRESSURE		●																												●														
WELL PUMP (SEE CIVIL DRAWINGS)										●				●						●												●			●			●			●	●		
DOMESTIC WATER SUPPLY																																										●		
FIRE PUMP ROOM PIPING SYSTEM																																										●		

INPUT/OUTPUT SUMMARY FOR PLUMBING AT END STATIONS (TYP 2)

SYSTEM, APPARATUS, OR AREA POINT DESCRIPTION	INPUTS: ANALOG MEASURED: TEMPERATURE	PRESSURE	RH	KW	AIR FLOW	LEVEL	GALLONS	INPUTS: ANALOG CALCULATED: KWH	ENTHALPY	RUN TIME	EFFICIENCY	WET BULB TEMP.	INPUTS: BINARY: STATOS	FILTER	SMOKE	FREEZE	AIR FLOW	METER	OUTPUTS: DIGITAL: OFF-ON	OFF-AUTO-ON	OFF-HI-LO	OPEN-CLOSE	MULTI-STAGE	OUTPUTS: ANALOG: DAMPER POSITION	VALVE POSITION	SET POINT ADJUSTMENT	VANE POSITION	SCR CONTROL	SYSTEM FEATURES: ALARMS: HI ANALOG	LOW ANALOG	HI BINARY	LOW BINARY	PROOF	SYSTEM FEATURES: PROGRAMS: TIME SCHEDULING	DEMAND LIMITING	DUTY CYCLE	START/STOP OPTION	ENTHALPY OPTION	SMOKE CNT.	TREND	ALARM INSTRUCT	MAINT. WK. ORD.	GENERAL: COLOR GRAPHIC	SUPPLEMENTARY NOTES
WASTE HOLDING TANK (SEE CIVIL DRAWINGS)						●																								●														
WATER STORAGE TANK, WT-01		●				●	●																								●														
DOMESTIC WATER PRESSURE		●																													●										●			
WATER SUPPLY SYSTEM																																										●		

LIGO-D961047-01-O

REFERENCES: DRAWING NO.	DESCRIPTION

REVISIONS: NO.	DATE	BY	CHKD	ENGR	PROJ	DESCRIPTION
1	8-7-98	DJB				ISSUED FOR AS-BUILT

ISSUED FOR CONSTRUCTION		
DRAWN	DG	11-15-96
CHECKED	ME	10-25-96
ENGINEER	AA	10-25-96
PROJ	TDM	11-15-96

AS-BUILT DRAWINGS

PARSONS
100 WEST WALNUT STREET
PASADENA, CALIFORNIA

LIGO
CALIFORNIA INSTITUTE OF TECHNOLOGY
MASSACHUSETTS INSTITUTE OF TECHNOLOGY

LASER INTERFEROMETER GRAVITATIONAL-WAVE OBSERVATORY
SITE NO.2 - LIVINGSTON, LOUISIANA

TITLE: PLUMBING CORNER & END STATION I/O SUMMARY

SCALE	CONTRACT NUMBER	PROJECT NUMBER
NONE	PP150969	8094

SHEET NUMBER: LA-P-002 REVISIONS: 1

LIGOLAF.BDR

This document and the design it covers are the property of PARSONS. They are loaned only with the borrower's expressed written agreement that they will not be reproduced, copied, loaned, exhibited, or used in any other way, except by written consent from PARSONS to the borrower.

Wed Oct 7 14:22:51 1998 c:\plot\def\S3-36.def N:\DUELUES\E30B2\MU0024.PRF