

# Detector Status

---

**David Shoemaker**

**27 Oct 98**

- Brief schedule/cost update
- Top-level status of each Detector subsystem
  - > design, procurement, fabrication
  - > technical highlights
- R&D activities for initial and advanced LIGO

# Detector Milestones

---

Milestone Description	Management Plan Date		Completion Date	
BSC Stack Final Design Review	04/98		08/98	
Core Optics Support Final Design Review	02/98		11/98	
HAM Seismic Isolation Final Design Review	04/98		06/98	
Core Optics Components Final Design Review	12/97		05/98	
Detector System Preliminary Design Review	12/97		10/98	
I/O Optics Final Design Review	04/98		03/98	
Prestabilized Laser Final Design Review	08/98		11/98	
CDS Networking Systems Ready for Installation	04/98		03/98	
Alignment (Wavefront) Final Design Review	04/98		07/98	
CDS DAQ Final Design Review	04/98		05/98	
Length Sensing/Control Final Design Review	05/98		07/98	
Physics Environment Monitoring Final Design Review	06/98		10/97	
Initiate Interferometer Installation	07/98 WA	01/99 LA	07/98 WA	01/99 LA
Begin Coincidence Tests	12/00		12/00	

# Detector Cost Status

<b>Subsystem</b>	<b>Budget</b>	<b>Cost and commitment</b>	<b>Estimate at completion</b>
Control and Data	13497	8787	13409
Physics Environ. Monitor	2196	1067	2052
Pre-Stabilized laser	3210	2728	3148
<b>Input Optics</b>	<b>1860</b>	<b>1886</b>	<b>2149</b>
Core Optics	8102	7517	7979
Core Optics Support	2021	812	1999
Alignment Sensing/Control	4820	2105	4589
<b>Length Sensing/Control</b>	<b>1695</b>	<b>1013</b>	<b>2049</b>
Suspensions	3443	1451	1714
<b>Seismic Isolation</b>	<b>11762</b>	<b>9664</b>	<b>13488</b>
Systems	2244	1886	2231
Support Equipment	1563	640	1566
<b>TOTAL</b>	<b>56414</b>	<b>39556</b>	<b>56372</b>

# Control and Data System (CDS)

---

## Function:

- communication infrastructure, data acquisition, individual subsystem control/monitoring (addressed with subsystem)

## Status:

- Final Design Review for Length/Alignment sensing for early 99
- all other Final Design Reviews complete and successful
- detailed layout/engineering/fabrication underway
- installation underway at Hanford

## LAN installed at Hanford

- system in use for scientific computing and facilities monitoring

## Vacuum controls finished

- complete and in use at Hanford
- being exercised as part of Vacuum Equipment installation at Livingston

## Data acquisition

- prototype complete and accepted



# Physics Environment Monitor

---

## **Function:**

- to monitor environment, provide veto and regression information; provide excitation to help characterize interferometer

## **Status:**

- Final Design Review complete; design complete except for cosmic muon detector
- first articles installed for several elements (residual gas analyzer, weather, excitation, stand-alone DAQ)
- installation paced by other activities: vacuum equipment, seismic isolation; all elements ready when needed

## **Support for seismic isolation first article tests**

- used to characterize dynamic performance
- sensors, excitation systems, DAQ employed/exercised

# Pre-Stabilized Laser

---

## Function:

- supplies the light to the interferometer, includes the 10W laser source; important element in the overall servocontrols approach

## Status

- **first article installed at Hanford (initiated installation of Detector)**
- testing of prototypes completed
- Final Design Review to take place in November '98




# Pre-Stabilized Laser

## Laser source

- source lasers showing good reliability
  - > 2000 hours, <3% drop in power
- now commercially available from Lightwave as '20 W laser'
- first 'option' laser in house - production running on schedule

## Prototype tests

- good 'standalone' noise performance
- high availability --- days of continuous operation of servosystems
  - > frequency stabilization servo, the PMC servo, the intensity servo and the temperature stabilization servo
  - > robust against environmental changes



# Input Optics

---

- temporal and spatial low-pass filtering of input light, matching of light into the interferometer; important element in servocontrol
- University of Florida has designed and is delivering/installing subsystem
- 2k suspensions completed, most optics in house
- installation for LHO 2k interferometer started, staging at Hanford

## Detection system for matching prototyped/tested

- bulls-eye sensor for circularly-symmetric modes
- dithering system allows independent test, calibration of wavefront sensor



## Large optics advancing nicely


- Test-mass sized last mirror presents manufacturing challenges
- long radius of curvature, usual size constraints
- polished, in-house, characterization in process



# Input Optics

---

## Setup of suspensions underway at Hanford



- Small Optics Suspension
- UFla and Hanford staff balancing one of the Input Optics



# Core Optics Components

---

- optics for the interferometer, test masses for the strain detection
- all core optics substrates procured, ground; only 6 left to polish, 16 to coat (out of 40)
- testing commencing for figure, loss, point defects
  - > 25-100 defects,  $>2.5$  microns ( $\sim 20$ ppm scatter)
- cleaning procedures in qualification

## In-house metrology

- initial interferometer vendor could not deliver, second vendor has had difficulty
- interferometer now in-house, accepted, and in tests/practice runs
  - > best repeatability of 0.2 nm,

## Some difficulties with coating

- improper cleaning at vendor, re-coating needed; improved QA now in place (LIGO personnel present for procedure)
- spares philosophy appears about right

## Overall development effort a smashing success

- polishing, metrology, and coating technologies all advanced
- LIGO requirements met or exceeded



# Core Optics Support

---

- Function: bring light out of interferometer for sensing/monitoring; contain scattered light; ‘dump’ unwanted beams
- Preliminary Design well advanced; Final Design Review in November
- detailed design of telescopes well advanced
- prototypes of parts installed in mock-ups



## **Wavefront flatness a challenge**

- Alignment sensors require small astigmatism, other distortions
- places strong requirements on beam-reducing telescopes
  - >  $0.7\lambda$  peak-valley phase flatness

## **Strong interaction with overall optics layout**

- baffling must accommodate pointing beams, ghost beams

- has driven (and contributed to) integrated optics layout



# Initial Alignment

---

- establishes the position and angle of optical components at moment of installation; maintain external pointing references to allow quick bootstrap to operational alignment, ease servicing work
- equipment for initial surveying in-house and qualified
- tests of basic procedures exercised at MIT
  - > 80 microrad initial alignment requirement easily fulfilled
- optical lever assemblies in fabrication or shipped

## Prototype tests


- stability of pointing system exceeds requirements
  - > 50 microrad peak over weeks requirement

## Interaction with facilities driven integrated layout

- Vacuum equipment: as-built viewports, deflections on pump-down
- Civil construction: placement of surveying markers, stability

# Alignment Sensing/Control

- maintains operational alignment
- prototype tests of sensors completed
- detailed soft/Hardware engineering underway
- details of transformation optics in design



## Use on suspended prototypes central to research

- Phase Noise Interferometer
- 40m Interferometer
- models confirmed quantitatively

## Digital servo

- 10 degrees-of freedom to sense, control
- requires fully multiple-input multiple-output system
- low bandwidth, but state changes, saturation, sharp filters
- in prototype tests

# Length Sensing/Control

---

- acquire, maintain the operational lengths for the interferometer; read out gravitational-wave strain
- now in detailed software development

## **Suspended interferometer test of digital control**

- MIT Phase Noise Interferometer demonstration (details under R&D)
- proof-of-practice for critical dynamic range and servo questions


## **Acquisition modeling well advanced**

- modifications but especially exploitation of dynamic model
- increases in calculated critical locking velocity of factor of 10
  - >  $3\lambda/\text{sec}$ ; implies locking in several seconds
- also progress on determining initial alignment requirements, with results comparable to earlier expectations

# Length Sensing/Control

## Modulation source

- comparison of commercial systems for phase noise
  - > best is not most expensive
- amplitude stabilization to below  $10^{-8} 1/(\sqrt{\text{Hz}})$  requirement





# Suspensions

---

- support test mass and other optics but not compromise thermal noise performance; provide actuators for positioning optics in angle and position
- Final Design Reviews and detailed design completed
- Small Optics Suspensions fabricated
  - > mechanical parts by University of Florida (used in Input Optics)
  - > electronics by Control and Data Systems
  - > in installation at Hanford
- Large Optics Suspension prototype iterated, now in production

## **Alternative means for attachments investigated**

- magnets attached to test masses, used as part of actuator system
- epoxy used to date; cleanliness and assembly time disadvantages
- exploring use of Indium

- > measurements indicate better thermal noise performance;  
roughly  $10^{-7}$  for Indium, factors 3-10 greater loss for epoxy

- Suspension installation fixture in initial setup and test



# Seismic Isolation

---


- provide attenuation of seismic noise in-band ( $>30$  Hz); provide actuation at microseismic peak (0.16 Hz); provide coarse positioning, drift compensation
- Final Design Reviews complete
- First article fit-check tests of both basic designs complete
  - > HAM (Horizontal Access Module - input optics)
  - > BSC (Basic Symmetric Chamber - test masses)
- some remaining issues/tests
  - > air-bearing (used as part of positioning)
  - > fine actuator and coarse actuator linkage
- fabrication underway for most parts
  - > complicated parts, complicated cleaning procedures
  - > installation rate will be limited by production rate



# Seismic Isolation

## First article tests of great value

- in addition to fit checks, fixturing; screw thread clearance; need for left handed springs...
- training for installation and tests of integration approach



- dynamic tests --- comparison with models very good

# Research and Development

---

## **R&D in support of the initial detector**

- largely complete
- efforts to provide ‘agile support’ for problems discovered in fabrication or field, for example
  - > tests of Indium bonding to test masses
  - > prototyping of digital controls
- 40m interferometer and Phase Noise interferometer work

## **Advanced R&D for future improvements to LIGO detectors**

- medium- and long-term research programs
- range from engineering obvious solutions to exploring inklings

# 40m Interferometer

---

## **Objectives:**

- experience with LIGO configuration on a suspended interferometer
- tests of data acquisition soft/hardware and diagnostics approaches

## **Difficulties**

- continued poor reliability of Argon laser
- recent loss of scientist leading effort
- re-focus on near term goals

## **Successes in automated alignment, using digital techniques**

- alignment control a pre-requisite for operation
- digital loop used to ease matrix transformation

## **Exercise of the dynamic model for locking**

- light storage time comparable to LIGO (high finesse cavities)
- allows comparisons with locking design code


## **Development of diagnostic techniques on LDAS/DAQ prototype**

- full LIGO data acquisition system
- real-time techniques as well as viewing/post-analysis tests created

# 40m Interferometer

## Development of probes of optical performance

- new ways to examine the mode structure of the cavities
- sweeping of modulation frequency, transmission/reflection analyzed



- excellent match of data and model for resonance form
- indication of lack of competing nearby modes to pull error signal


# Phase Noise Interferometer

## Objectives:

- phase noise demonstration: successfully completed
- tests of digital servoloop technology, real time diagnostics
- tests of photodetection system

## Configuration

- power-recycled Michelson
- very similar dynamic range, intensity demands to those in LIGO
- digital filter function/gain replaces analog system
- second crate linked via reflective memory





# Phase Noise Interferometer

---


## Servoloop tests

- similar loop gains, noise performance to (excellent) analog system
- resonant gains, adiabatic transfer function changes, state switching for acquisition tested successfully

## Status

- demonstration complete, lessons learned passed on to design team
- system dismantled with MIT move in July

- chambers now used in other experiments



# Advanced R&D

---

## INTERFEROMETER CONFIGURATIONS

- Objective: explore means to tune the frequency response of advanced detectors to match instrument or astrophysical signatures
  - > demonstrate Resonant Sideband Extraction on a tabletop  
Technique: addition of output recycling mirror to make gravitational wave sidebands resonant or anti-resonant
- Experiment: table-top prototype experiment using a control scheme which could be employed in LIGO
- James Mason, CIT graduate student, leading experiment

### Status:

- modeling complete; start of construction of system in June
- lab set up, mirror mounts/actuators built, electronics controls designed, built, and tested
- 3-mirror cavities locked, more components being added
- anticipated February '00 completion with planned outcome a recommended design for LIGO

# Advanced R&D

## SAPPHIRE TEST MASS DEVELOPMENT

- Objective: to push technology of sapphire as optical and mechanical element for advanced LIGO designs
- Technique: international collaboration (VIRGO, ACIGA) to push fabrication techniques, characterize materials

### Status:

- Materials procured from Crystal Systems, and China Institute of Optics (SIOM)



- Characterization of optical absorption losses in ACIGA, Stanford, VIRGO; range of values, but generally higher than anticipated (100 ppm/cm), feedback given to producers on some suspects
- General Optics polished a 15cm dia surface; difficulties in obtaining a reasonable figure due to bulk fault(s), will try again with new sample
- Mechanical Q testing performed at Caltech
  - >  $Q_s$  greater than  $1 \times 10^7$  seen, but many lower
  - > iterating suspension technique, excitation system

# Advanced R&D

---

## **THERMAL NOISE INTERFEROMETER**

- Objective: direct measurement of thermal and excesses in realistic suspension systems
- Technique: short-baseline special-purpose interferometer
  - > makes seismic noise ‘common-mode’
  - > relaxes laser frequency-noise requirements
- first measurements on LIGO-I like suspensions
  - > allows learning curve with familiar wire loop
  - > can help debug LIGO-I problems
- later work with advanced LIGO components (fused quartz suspensions)

# Advanced R&D

## **THERMAL NOISE INTERFEROMETER Status**

- the pre-stabilized laser has been assembled and tested with a second reference cavity, and functions well



- vacuum chamber and stack (from the Phase Noise Interferometer) are in assembly;
- taken delivery of all the significant optics
- optics suspensions and controls in design/construction
- plan to collect first complete data by December '98

# Advanced R&D

---

## SUSPENSIONS

- Objective: reduced thermal noise and better isolation for near-term LIGO enhancements
- Technique: incorporation of a fused-quartz suspension, re-allocation of actuator authority
- Experiment: tests of prototypes; ultimately full-scale engineering tests
- Status: infrastructure coming together; design work underway

- Full-scale Advanced System Test Interferometer installation  
November 2

**First tests in smaller vacuum system:**

- tests of GEO suspension
- charge control
- tests of sample pre-isolator
- December start of shakedown/tests

First results by  
March '99







# Advanced R&D

## ISOLATION

- Objective: exploration of techniques for advanced seismic isolation
- Technique: redesign and test of VIRGO-like isolation systems
- Experiment: tests of vertical isolation system
- Status: prototype designed, assembled, in first test
  - > low vertical resonant frequencies achieved
  - > sensitive parameters explored



# Advanced R&D

---

## **FUSED QUARTZ SUSPENSION FIBER DEVELOPMENT**

- Plan to develop means to produce reliable reproducible fibers
- ‘lathe’ on order, lab being set up, modeling underway

## **ADAPTIVE OPTICS**

- Plan to develop correction for thermal lensing in test mass substrates, due to absorption of laser beam in substrate and on surface
- experiment in construction (in Phase Noise Interferometer vacuum tank), MIT Grad (Ryan Lawrence) leading effort
- first results in March ‘99

# Detector: Summary

---

**Design very nearly complete**

**Prototyping and first article testing very nearly complete**

**Fabrication started for most subsystems**

**Detector effort still (essentially) on schedule and no significant problems**

**The challenge, and excitement, is becoming the installation**